

Carnegie Mellon University

Heinz College-Hamburg Hall Addition Campus Town Hall Meeting

Agenda

- Introductions

- Schedule 4.
 - Impacts
- 6.

2. Heinz College Project Overview 3. Program & Design Questions & Answers

December 3, 2014

Introductions

- Design Team: GBBN Architects Civil & Environmental Consultants, Inc - Civil Engineering Allen & Shariff - Mechanical, Electrical & Plumbing Engineering Buro Happold - Structural Engineering evolveEA - LEED Consultants
- Construction Management Firm: Mascaro Construction Company
- Heinz College and Campus Stakeholders
- Campus Design & Facility Development



Existing Courtyard

Existing Courtyard - Rotunda

Existing Courtyard - Smith Hall

Hamburg Hall Addition to focus on adding a new 150 seat Lecture Hall, group and individual study space, student project rooms and a cafe.

completed

Phase 2 - 150 seat Lecture Hall, Rotunda renovations, and building code and access upgrades

Phase 2.5 - Provide flexible classrooms to allow for innovative and progressive learning.

Phase 3 - Enclose courtyard with glass roof providing student space and a cafe for Heinz College students.

Phase 4 - Interior office renovations

Project Overview

Phase 1 - Interior office renovations have been

Heinz College - Phase 2

Begins December 15, 2014

Heinz College A-LEVEL PLAN-Ph2

- 150 Seat Lecture Hall
- New Forbes Entrance
- Code & Corridor Upgrades

Heinz College A-LEVEL PLAN-Ph2

- 150 Seat Lecture Hall
- Collaborative Seating

Heinz College Accessibility & Landscape Plan

BUS STOP PLANTER LAWN 1:12 RAMP CONCRETE STAIR/WALK BENCHES GLASS VESTIBULE DROP-OFF

Heinz College Forbes Ave - Accessible Entry

Forbes Avenue

Heinz College FIRST FLOOR PLAN-Ph2

- Rotunda Renovation
- Exterior Plaza

Heinz College Main Lobby

Carnegie Mellon University | Heinz College

-

.....

-

Carnegie Mellon University | Heinz College

X

Heinz College Code Upgrades

 \bullet

 \bullet

Fire Suppression Keep Aesthetic of Existing Handrails New Glass Guardrails Stainless Steel Handrails

Heinz College - Phase 2.5

Will commence after Scott Hall is completed

Forbes Avenue

Heinz College FIRST FLOOR PLAN-Ph2.5

- 4 Flex Classrooms
- **Executive Education** Classroom
- 2nd Floor West Wing • Faculty & PhD Offices

Heinz College - Phases 3 & 4

Not yet funded --- Still in the planning phase

Heinz College A-LEVEL PLAN

- Student Social Space
- Cafe
- 150 Seat Lecture Hall \bullet
- Group Study ${\color{black}\bullet}$
- **Project Rooms**
- Corridor Upgrades
- Cistern
- **Bio-retention**
- New Forbes Entrance

Carnegie Mellon University | Heinz College

Carnegie Mellon University | Heinz College

The project embodies fundament principles of sustainable design.

Stormwater management via bio-retention areas and gray water cistern collection and reuse.

Renovated toilet rooms will utilize low-flow fixtures and gray water from the cistern.

Demand control ventilation within new Lecture Hall as well as the use of energy recovery units on new mechanical systems

Use of locally manufactured materials

Low-emitting construction materials

Glass atrium roof will provide ample daylight. Glass to be selected with proper shading coefficient to relieve excess strain on mechanical systems.

Enhanced commissioning of project

Radiant cooling slab. The floor of the atrium will contain piping with a refrigerant which will absorb and remove heat from the space.

The Lecture Hall will achieve LEED Silver Certification while the atrium and remainder of Hamburg Hall will be built to fundamental standards of sustainable design.

Heinz College SUSTAINABILITY OVERVIEW

Site Logistics Planning

Mobilization

December 15, 2014 through January 2, 2015

- Shut down courtyard
- Protect windows with insulation and plywood
- Install site fencing
- Set-up construction trailers
- Re-locate temporary generator to south end of west wing
- Re-locate bike racks to CIC (north end)

Excavation and Selected Demolition

January 2, 2015 through March 30, 2015

- Excavate the classroom building foundations within the courtyard
- Excavate trenches for the site utilities within the courtyard and between Smith Hall and Newell Simon Hall
- Excavate for cistern and piping within the courtyard
- Excavate trenches for electrical ductbank inside A-Level of Hamburg Hall at the rear entrance (west end)
- Demolish Floor 1 nook (west end) to create new mechanical room for the new classroom building

Effects of Early Phases of Construction

- The geotechnical analysis shows that all excavation will be through rock
- Heavy equipment will be used for rock excavation, causing loud noise, vibration, and dust
- Diesel-powered tri-axle trucks and loaders will be utilized for the removal of excavation spoils
- Interior hallways will be disrupted with utility trenching

Interruption Mitigation Measures

- Excavation work will be scheduled from 10PM to 8:30AM
- The windows of Hamburg Hall and Smith Hall directly adjacent to the classroom foundation work will be covered with sound insulation and plywood
- Other selected windows will be covered with 6 mil plastic for dust protection
- Install filter fabric on building air intakes
- Trenches will be backfilled or plated to allow access after 8:30AM

Window Protection at Smith Hall

Window Protection at Hamburg Hall (East/West)

Window Protection at Hamburg Hall (South)

Continued Renovations

- The new classroom building is scheduled to be completed for the fall of 2015
- Interior renovations of the Rotunda (A-Level and Floor 1), corridor upgrades, building life safety improvements (including fire alarms, sprinklers, and stairwell fire enclosures), new bathrooms, and new ADA entrance off of Forbes Avenue are scheduled to be executed between May, 2015 and February, 2016

Continued Communication

 A website will be brought online for the project in the next couple of weeks in order to keep the campus community informed of happenings on the project:

http://www.cmu.edu/cdfd/heinz-hamburg-hall/

 Updates will be provided on a regular basis and shutdowns / service interruptions will be scheduled with adequate advance notice

Questions & Answers